





SIDEWALK ADJACENT TO CURB



SIDEWALK NOT ADJACENT TO CURB

1/4" PER FOOT SLOPE (2%) CURB TO BACK OF WALK EXCEPT AT DRIVEWAY/ALLEY APPROACHES ONLY.

NOTES:

1. CONCRETE SHALL BE STATE CLASS "B" (5 SACK, 1" ROCK).
2. INSTALL 1/2" FELT EXPANSION JOINT AT CURB RETURNS AND AT 60' O.C.
3. PLACE WEAKENED PLANE JOINTS AT 10' O.C.
4. JOINTS IN CURB AND IN ADJACENT SIDEWALK SHALL MATCH.
5. CURB FACE SHALL BE 6" UNLESS OTHERWISE SPECIFIED.
6. MONOLITHIC POUR OF CURB, GUTTER AND SIDEWALK IS NOT ALLOWED.

ENGINEERING DEPARTMENT		CITY OF MERCED, CA.	
SIDEWALK, CURB & GUTTER SECTION			SCG-1
DRAWN: KGE	APPROVED BY: <i>David L. Tucker</i>	DATE: 3/17/08	
DATE: 12/05			
REVISED: 3/17/08	CITY ENGINEER	SHEET	OF