

CITY POLICIES

1. TEMPORARY LIGHTNING – WHERE VANDALISM MAY BE PREVALENT DURING CONSTRUCTION WORK, THE DEVELOPER MAY ARRANGE TO PAY THE ENERGY CHARGES FOR SHORT-TERM LIGHTING SERVICE ON A FLAT RATE PER MONTH PER LUMINAIRE BASICS. ARRANGEMENTS MAY BE MADE THROUGH THE CITY ENGINEER'S OFFICE.
2. PARTIALLY COMPLETED STREET LIGHTING SYSTEMS WITHIN SUBDIVISION WILL NOT BE ACCEPTED BY THE CITY FOR MAINTENANCE UNTIL FULL IMPROVEMENTS HAVE BEEN COMPLETED. THE DEVELOPER WILL BE RESPONSIBLE TO MAINTAIN THE LIGHTING SYSTEMS UNTIL ACCEPTANCE BY THE CITY.
3. THE CITY WILL ASSUME ENERGY COST FOR LIGHTING ONLY AFTER RESIDENCES OR BUILDINGS HAVE BEEN GREEN TAGGED AND ARE READY FOR OCCUPANCY, OR AS MAY BE DETERMINED BY THE CITY ENGINEER AS BEING IN THE BEST INTEREST OF THE GENERAL PUBLIC.
4. EQUIPMENT SUBMITTALS – SUBMITTALS WILL BE REQUIRED FOR ALL STREET LIGHTING ON PUBLIC PROPERTY. NO CONSTRUCTION WILL BE PERMITTED UNTIL SUBMITTALS HAVE BEEN APPROVED BY THE CITY ENGINEERING DEPARTMENT.
5. SPECIAL LIGHTING APPLICATIONS – LIGHTING APPLICATIONS IN UNCLASSIFIED AREAS OR THE USE OF MIXED STANDARDS SHALL HAVE PRIOR CONCEPT APPROVAL. CONSULT THE CITY ENGINEERING DEPARTMENT.
6. DEVELOPER'S RESPONSIBILITY – IT SHALL BE THE DEVELOPER'S RESPONSIBILITY TO FULLY COMPLY WITH PG&E COMPANY'S REQUIREMENTS AND TO PAY ALL CONNECTION FEES AND SERVICE CHARGES IMPOSED AND TO EXTEND ALL STREET LIGHTING SERVICE CONDUCTORS TO SERVICE POINTS AS WILL BE INDICATED BY PG&E COMPANY ON THEIR ELECTRICAL DISTRIBUTION DRAWINGS. PG&E COMPANY MUST RECEIVE FINAL COPIES OF THE IMPROVEMENT PLANS BEARING THE SIGNATURE OF THE CITY ENGINEER BEFORE THEY CAN FINALIZE THEIR DISTRIBUTION DRAWINGS.
7. ANY CIRCUIT OR EQUIPMENT FOUND TO BE MALFUNCTIONING AFTER BEING ENERGIZED SHALL BE CORRECTED BY THE CONTRACTOR WITHIN 10 WORKING DAYS AFTER RECEIVING WRITTEN NOTICE FROM THE CITY. THIS ORDER SHALL REMAIN IN FORCE UNTIL FINAL ACCEPTANCE BY THE CITY.
8. PHOTO CELLS TO BE COVERED (OR SHORT CAP INSTALLED) AND LIGHTS TO "BURN IN" FOR MINIMUM 72 HOURS UPON ENERGIZING, TO VERIFY OPERATION. SHORTING CAP OR PHOTO CELL TO BE REMOVED IMMEDIATELY AFTER 72 HOUR PERIOD.
9. CONTRACTOR SHALL STENCIL NUMBERS ASSIGNED BY THE CITY ON THE STREET SIDE OF THE POLE AT $\pm 48"$ ABOVE FINISH GROUND. 2" STENCIL WITH GLOSS BLACK PAINT.

ENGINEERING DEPARTMENT		CITY OF MERCED, CA.		
STREET LIGHT STANDARDS		SL-3		
DRAWN: AV	APPROVED BY: <i>David L. Tucker</i>			DATE: 4/4/06
DATE: 05/05				
REVISED:	CITY ENGINEER	SHEET OF		